S.NO.	ITEMS	QUANTITY	UNIT	REMARK		
1	EarthWork					
	Site Cleaning	287.1	Sqm			
	Excavation		<u> </u>			
	Up to 1.5m	130.680	cum	Excavation Qty. is		
	Above 1.5m	43.560	cum	Measured in two parts as		
	Sand filling	8.712	cum			
	Back filling	132.380	cum			
	Plinth Filling	100.432	cum			
2	Cement Concrete	(Plain & F	Reinfor	ced)		
	P.C.C. (Below footing M-10)	8.712	cum			
	Floor P.C.C. (M-15)	12.554	cum			
	Footing Concrete (M-25)	20.996	cum			
	Pedestal Column Concrete (M-25)	3.440	cum			
	Ground Beam Concrete (M-25)	9.638	cum			
	Column Concrete for Sub- Structure Part (M-25)	2.160	cum			
	Column Concrete for Super- Structure Part (M-25)	7.200	cum			
	Sill Band Concrete (M-25)	1.324	cum			
	Lintel Beam Concrete (M-25)	3.104	cum			
	Slab Beam Concrete (M-25)	11.454	cum			
	Slab Concrete (M-25)	11.678	cum			
	Staircase Concrete (M-25)	1.930	cum			
	D.P.C For Sub-Structure Part	1.606	cum			
	D.P.C For Super-Structure Part	0.662	cum			
	Bitumin Coat	32.130	Sqm			
3	Reinforcement					
	All Rcc Members	8022	kg	110Kg/Cum		

4	FormWork					
	Footing Shuttering	38.40	Sqm			
	Pedestal Column Shuttering	44.72	Sqm			
	Ground Beam Shuttering	77.10	Sqm			
	Column Shuttering For Sub-		Sam			
	Structure part	28.08	Sqm			
	Column Shuttering For Super-		Sqm			
	Structure part	93.60				
	Sill Band Shuttering	16.08	Sqm			
	Lintel Beam Shuttering	44.28	Sqm			
	Slab Beam Shuttering	104.65	Sqm			
	Slab Shuttering	116.78	Sqm			
	Staircase Shuttering		Sqm			
5	BrickWork					
	One Line BrickWork For		O			
	Ground Beam	3.213	Cum			
	BrickWork up to DPC bottm		Cum			
	Brief work up to Br e settin	14.456	- Cuiii			
	Entrance Step	1.35	Cum			
	One Line BrickWork For Super		Cum			
	Structure (200mm Wall)	1.040	Cum			
	BrickWork up to sill band		Cum			
	Bottom (200mm Wall)	6.760	<u> </u>			
	BrickWork up to Lintel Level		Cum			
	(200mm Wall)	8.160	Cum			
	BrickWork up to Slab Beam		Cum			
	Bottom (200mm Wall)	4.046				
	One Line BrickWork For Super		Sqm			
	Structure (100mm Wall)	2.84	Sqiii			
	BrickWork up to sill band		Sqm			
	Bottom (100mm Wall)	18.46				
	BrickWork up to Lintel Level		Sqm			
	(100mm Wall)	34.08	- Sqiii			
	BrickWork up to Slab Beam		Sqm			
	Bottom (100mm Wall)	12.88	oqiii			
6	Plastering Work					
	6mm plaster surface	138.16	Sqm			
	12mm plaster surface	272.73	Sqm			
	15mm Inner plaster surface	139.49	Sqm			
	15mm outer plaster surface	200.44	Sqm			

7	Painting Work					
	White Wash	750.82	Sqm			
	Putty	750.82	Sqm			
	Primer	750.82	Sqm			
	Inner Paint	550.38	Sqm			
	Outer Paint	200.44	Sqm			
8	Steel & Aluminium Work					
	Aluminium Fixed Frame	65.74	Kg			
	Aluminium Sliding Frame	91.58	Kg			
	Glass	21.60	Sqm			
	Mosquito Net	10.80	Sqm			
	Window Grill	279.46	Kg			
9	Flooring					
	Kota Stone	20.27	Sqm			
	Vitrified Tiles	120.74	Sqm			
	Ceramic Tiles	118.35	Sqm			
	Granite	23.56	Sqm			
	Nosing (Moulding)	33.15	Meter			
10	<u> </u>	O WORK				
	Door Frame		Cum	Subtract the		
		0.640		Qty. of D3		
	Door Shutter (panelled door)	6.32	Sqm	D1 & MD		
				Door		
			0	Its Include		
	Door Shutter (Flush door)	15.19	Sqm	D2 Door		
	Door Shutter (FRP door) With		Sqm	Its Include		
	Door Frame	5.09		D3 Door		
	L-Drop (300 X 16mm)		Each			
	B-Drop (300 X Tollilli)	16	Dacii			
	Tower Bolt (250 X 10mm)	31	Each			
	Handle (125mm)	34	Each			
	Door Holder (Triple strip		Each			
	vertical type.)	17	Lacii			
	Door Stopper (150mm)	13	Each			
	Hinges (125x85x5.50mm		Each			
	(Heavy Type))	52	Lacii			
	Hook (300 mm)	4	Each			